















## PECAN GROVE MODULAR UNIT STANDARD SPECIFICATIONS

- ❖ Steel I-Beam Chassis with Removable Hitch, Axles & Tires
- ❖ 2X6 Southern Yellow Pine Floor Joists (16-Inches on Center)
- R-22 Floor, R-19 Wall & R-30 Roof Insulation
- ❖ 3/4-Inch Advantech Subfloor Glued, Stapled and Screwedt
- Full House Moisture Barrier
- Woodgrain Vinyl Flooring
- ❖ Low-E Vinyl Windows
- ❖ Fiber Cement Board Exterior Siding (Painted or Stained)
- Shingles Roof
- 2X4 (16-Inches on Center)
- Premium Faucets in a variety of finishes
- ❖ 54-Inch Shower

- Exterior GFI Outlet
- LED Interior Lights
- Ceiling Fan in Living Area
- Solid Wood Cabinetry with Raised Panel Doors
- ❖ 40-Gallon Electric Water Heater
- 200-Amp Electric Panel
- Full-size Appliances (Refrigerator, Stove, and Microwave with Range Hood)
- Laminate Countertops

- Fiberglass Exterior Doors with Privacy Blinds
- ❖ 1- 4 Zone Mini Split AC System (Installed)
- Exterior Faucet
- Vinyl Wrapped Drywall (VOG-Vinyl over Gypsum)
- White Trim Package (Base and Crown)

## **AVAILABLE OPTIONS**

- LVP Flooring
- Solid Surface Counters
- On Demand Water Heater
- Stainless Appliance Package
- Finished and Painted Sheetrock Interior